

| TRENCH MATERIAL | REMOVABLE FORMING SYSTEM |
|-----------------|-----------------------------------|
| FRAME MATERIAL | T304 STAINLESS STEEL |
| FRAME COATING | NONE |
| ANCHOR STUDS | 3" X 3/8" Ø |
| INSTALL DEVICE | RIGID STAMPED METAL FOR #4 BARS |
| LOAD RATING | HEAVY DUTY |
| SLOPE | 0.5% TYP (CUSTOM SLOPE AVAILABLE) |

STANDARD TOLERANCES 0 = +/-0.25 0.0 = +/-0.25 0.00 = +/- 0.13

SIDE VIEW

NOTE: ALL TRENCHES ARE FACTORY ASSEMBLED AND READY FOR SITE INSTALLATION



574c Industrial Way N. Dallas, GA 30132 PH: 770-505-6575 www.trenchdrain.net